



NOTE:

1. TRACK ASSEMBLY SHOWN, IS LEFT SIDE OF PAVER AS VIEWED FROM OPERATORS POSITION.



PAVER TRAVEL

2. PART NO. 52, IS THE COMPLETE TRACK UNDERCARRIAGE ASSY. WITH TRACK AND WHEELFRAME GROUP COMPLETE.

	7 0 8	TRACK ASSY. (COMPLETE) R.H.	1	
	7 0 L	TRACK ASSY. (COMPLETE) L.H.	1	
22	6 5 8	WHEEL FRAME (RIGHT SIDE)	1	D
21	5 0 0 - 0 0 0	HEX NUT 1/2-13 NC	0	
20	3 6	UNDERCARRIAGE FRAME (FOR TRACKS)	1	D
19	5 0 0 - 2 6 2	HEX HEAD CAPSCREW 1/2-13 X 1" L.G.	2	
18	8 7	TRACK FRAME PIN WASHER	2	D
17	6 5 L	WHEEL FRAME (LEFT SIDE)	1	D
16	5 0 0 - 2 2 5	HEX HEAD CAPSCREW 3/4-10 X 1 1/4" L.G.	4	D
15	6 8	TRACK WHEEL W/BUSHING	4	D
14	7 7	IBLER ROLLER W/BUSHING	2	D
13	7 0	WHEEL BUSHING	12	
12	7 1	AXLE	6	D
11	5 0 0 - 2 5 5	TRACK ADJUSTING SCREW	4	D
10	5 0 0 - 2 2 6	STD. LOCKWASHER 3/4"	12	
9	7 4	HEX HEAD CAPSCREW - (SPECIAL)	6	D
8	5 0 0 - 1 7 6	GREASE FITTING 1/8 HPT STRAIGHT	6	
7	8 6	WHEEL FRAME PIN	2	D
6	5 0 0 - 1 8 9	STD. FLAT WASHER 1/2"	2	
5	5 0 0 - 0 5 0	STD. LOCKWASHER 1/2"	2	
4	5 0 0 - 3 2 L	HEX HEAD CAPSCREW 1/2-13 NC X 3/4" L.G.	2	
3	6 7	PAVER TRACK ASSEMBLY	2	D
2	6 8	TRACK CONNECTING PIN ASSY.	2	D
1	5 0 0 - 2 0 0	SOCKET HEAD SETSCREW 3/8-16 X 3/8"	2	

140151

LAYTON MANUFACTURING COMPANY
SALINA, OREGON

TITLE: PAVER TRACK ASSEMBLY

REV. 7-85

PROJECT: PAVER H-500 DRAWING NO: D-870